

Date: Tuesday, 03/03/2009 4:12:28 PM
 User: Julie Dawson

Process Sheet

Customer : CU-DAR001 Dart Helicopters Services	Drawing Name : STRUT WELDMENT ASS'Y
Job Number : 46261	
Estimate Number : 11515	
P.O. Number :	Part Number : D34439
This Issue : 03/03/2009 S.O. No. :	Drawing Number : D3443 REV. B.
Prsht Rev. : NC	Project Number :
First Issue : / / Type : MACHINED PARTS	Drawing Revision : B
Previous Run : 46131	Material :
Written By :	Due Date : 20/03/2009 Qty: 10 Um: Each
Checked & Approved By : <u>JUD 09.03.04</u>	
Comment : est rev A 05.12.19 new issue ec	

Additional Product

Job Number:



Seq. #:	Machine Or Operation:	Description :
----------------	------------------------------	----------------------

1.0	MDELNRINR0500	Delrin Round Bar .50"
-----	---------------	-----------------------



099 A(s)/Unit

099 A(s)



Comment: Qty.: ~~0.0010 f(s)/Unit~~ Total : ~~0.9100 f(s)~~

Delrin Round Bar .50"

batch: 4109341

SA 09/03/06

2 feet (no toes)

2.0	HARDINGE	HARDINGE CNC LATHE SMALL
-----	----------	--------------------------



Comment: 1-TURN AS PER FOLIO FA698 & DWG D3443 ,

FOLIO REV: BDWG REV: B

2-DEBURR AS REQUIRED

SA 09/03/06

(10)

3.0	QC2	INSPECT PARTS AS THEY COME OFF MACHINE
-----	-----	--



Comment: INSPECT PARTS AS THEY COME OFF MACHINE

SA 09/03/06

(10)

4.0	QC8	SECOND CHECK
-----	-----	--------------



Comment: SECOND CHECK

mm/mm 09/03/06

(11)

5.0	PACKAGING 1	PACKAGING RESOURCE #1
-----	-------------	-----------------------



Comment: PACKAGING RESOURCE #1

Identify and Stock

Location: ST 93

JS 09/03/09 (xu)

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes No DQA: _____ Date: _____

Resolution: _____ Disposition: _____ QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

NOTE: Date & initial all entries

Date: Tuesday, 03/03/2009 4:12:28 PM
User: Julie Dawson

Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: STRUT WELDMENT ASS'Y

Job Number: 46261

Part Number: D34439

Job Number:



Seq. #:

Machine Or Operation:

Description :

6.0

QC21

FINAL INSPECTION/W/O RELEASE



09/03/09

Comment: FINAL INSPECTION/W/O RELEASE

Job Completion



MR
09-03-09

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes No DQA: _____ Date: _____

Resolution: _____ Disposition: _____ QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			


NOTE: Date & initial all entries





DESIGN RF	DRAWN BY RF	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED #	APPROVED #	DRAWING NO. D3443	REV. B SHEET 1 OF 3
DATE 05.12.05		TITLE STRUT WELDMENT ASSEMBLY	SCALE 1:4
A	05.09.02	NEW ISSUE	
B	05.12.05	ADDED -9 PIN; REMOVED BALL PLUNGER; REVISE TOLERANCE; & Ø0.125 WAS #30	

RELEASED




05.12.09



PRESS FIT McMASTER-CARR P/N 63215K32
BALL JOINT BEARING AFTER POWDER COAT



D3443-041



D3443-043

SHOP COPY
RETURN TO
ENGINEERING

NOTES:

- 1) WELD PER DART QSI 004
- 2) FINISH: POWDER COAT WHITE (4.3.5.2) PER DART QSI 005 4.3
- 3) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) ALL DIMENSIONS ARE IN INCHES
- 5) IDENTIFY WITH DART P/N USING FINE POINT PERMANENT INK MARKER

UNCONTROLLED COPY

SUBJECT TO AMENDMENT



WITHOUT NOTICE

WORK ORDER




NO. 46261

COPYRIGHT © 2005 BY DART AEROSPACE LTD.

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.



1) MATERIAL: 17-4 SS PER AMS 5604/5643 (REF DART SPEC M17-4B)



D3443-3 CLEVIS

1) MATERIAL: AISI 304 SS ROUND BAR (REF. DART SPEC M304R)

2) FINISH: NONE
3) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
4) ALL DIMENSIONS ARE IN INCHES
5) BREAK ALL UNMARKED SHARP EDGES 0.005 TO 0.010

NO. 46261


COPYRIGHT © 2005 BY DART AEROSPACE LTD.

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.



DESIGN RF	DRAWN BY RF	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED 	APPROVED 	DRAWING NO. D3443	REV. B SHEET 3 OF 3
DATE 05.12.05		TITLE STRUT WELDMENT ASSEMBLY	SCALE 1:2

$\phi 0.210^{+0.005}_{-0.010}$



D3443-9 PIN

D3443-9 NOTES:



- 1) MATERIAL: DELRIN II 150R OR ACETRON GP ACETAIL (REF. DART SPEC M-DELRIN-R)
- 2) FINISH: NONE
- 3) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) ALL DIMENSIONS ARE IN INCHES

RELEASED

05.12.09






DRILL $\phi 0.125$ THRU
CHAMFER 0.025 (TYP)



D3443-5 TUBING

$0.260^{+0.000}_{-0.030}$



DRILL $\phi 0.125$ THRU
CHAMFER 0.025

D3443-7 TUBING

D3443-5/-7 NOTES:

- 1) MATERIAL: AISI 316/304 SS SEAMLESS TUBING (REF. DART SPEC M304TR0.7500W.120)
- 2) FINISH: NONE
- 3) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) ALL DIMENSIONS ARE IN INCHES
- 5) BREAK ALL UNMARKED SHARP EDGES 0.005 TO 0.025

SHOP COPY
RETURN TO
ENGINEERING

UNCONTROLLED COPY
SUBJECT TO AMENDMENT
WITHOUT NOTICE
WORK ORDER
NO. 410261

COPYRIGHT © 2005 BY DART AEROSPACE LTD.

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.